

**ITEM 0102011**

**REMOVE CONCRETE WALK**

**DESCRIPTION**

This item shall include excavation, removal and disposal of existing concrete walk, furnishing material for and backfilling, in the areas except where new concrete walk will be constructed as indicated on the plan.

**REFERENCED ITEMS**

None

**REQUIRED SUBMITTALS**

None

**MATERIALS**

**CONSTRUCTION METHODS**

1. **EXCAVATION AND BACKFILLING**

The excavation shall be to a maximum depth of 17" and to a minimum of 4" outside the edge of the walk. All the excavated area shall be filled with suitable backfill material as approved by the engineer (no clay), free of sticks, stones and rubble to 6" below finished ground level at no extra cost to the City. The backfilling shall be done in a manner to eliminate future settlement.

2. **CLEAN UP**

Upon suspension or completion of the work or any part thereof, the Contractor shall dispose of all removed materials, rubbish, remove equipment and leave the work area in a neat and orderly condition. During the progress of the work, the premises shall be kept clean, presentable and satisfactory to the Engineer.

**METHOD OF MEASUREMENT**

This work will be measured for payment by the square foot contract unit price for Remove Concrete Walk as required by the drawings, to the satisfaction of the Engineer.

**BASIS OF PAYMENT**

This work will be paid for at the contract square foot price for "REMOVE CONCRETE WALK" complete, which price shall include excavation, removal and disposal of the existing concrete walk, backfilling and compacting, equipment, tools and labor incidental thereto.

<b><u>PAY ITEM</u></b>	<b><u>DESCRIPTION</u></b>	<b><u>PAY UNIT</u></b>
0102011	Remove Concrete Walk	SF