

**ITEM 0102921**

**NEW FLAGSTONE WALK**

**DESCRIPTION**

Work under this item shall include furnishing materials, equipment, and labor for installing new flagstone walk to line and grade, furnishing new foundation where necessary to construct new flagstones walks, filling joints and adding topsoil, grading and seeding where necessary along the walk edges.

**REFERENCED ITEMS**

Item 0106401

**REQUIRED SUBMITTALS**

None

**MATERIALS**

Color of the flagstones shall be in the light to medium grey color range, closely matching the existing flagstone, and shall be of standard size and shape with a length of 5 feet in each direction. Sand, for the base, shall be well graded and of such size that all will pass the No. 8 sieve.

**CONSTRUCTION METHODS**

The flagstones shall be carefully removed and the stone base regraded as required using the existing material or new sand shall be added if necessary. The flagstone shall be set to proper line and grade and they shall be firmly bedded in the foundation so that no voids occur underneath them and the joints shall be completely filled with sand.

The contractor shall exercise care in the handling of the flagstones to avoid damaging them and shall use equipment necessary to lift the flagstones only from the edges of the walk and not between adjoining flagstones.

If damage to the flagstones does occur due to the contractor's negligence, as determined by the Engineer, he shall replace them with flagstones in good condition at his own expense.

The Contractor shall backfill along the edges of the flagstones with topsoil. The topsoil shall be graded to match the exist grade. Fertilizer, seed, lime, and mulch

shall be complete in conformance with the requirements of Item 0106401 - Topsoil, Fertilizing, Seeding, and Mulching. No additional payment will be made for restoration of turf adjacent to reset flagstone walks

**METHOD OF MEASUREMENT**

New flagstone walk will be measured for payment by the number of square feet of walk completed and accepted by the Engineer.

**BASIS OF PAYMENT**

This item will be paid for at the contract unit price per square foot for "NEW FLAGSTONE WALK" complete in place which price shall include all materials, tools, equipment, labor and work incidental thereto.

<b><u>PAY ITEM</u></b>	<b><u>DESCRIPTION</u></b>	<b><u>PAY UNIT</u></b>
0102921	Install New Flagstone Walk	SF