

ITEM 0107201

CONSTRUCTION SIGNS

DESCRIPTION

Under this item, the Contractor shall erect, maintain, move, adjust, relocate, and store all construction signs (and their supports) or metal sign posts required on the project to conform to the signing requirements stated and shown on the Traffic Phasing Drawings and/or directed by the Engineer. The Contractor shall furnish a sufficient number of signs to provide the signing patterns for all operations being undertaken concurrently.

REFERENCED ITEMS

Item 0107601

REQUIRED SUBMITTALS

Material Certificate of Compliance:

Submit 5 copies of material certificate of compliance for reflective sheeting in accordance with the contract general requirements.

MATERIALS

Signs and their portable supports or metal posts shall conform to the requirements as shown on the plans and the latest edition of the Manual of Uniform Traffic Control Devices. Drawings of the signs showing placement and dimensions of legend and border are available in the Standard Construction Details.

Reflective sheeting shall comply with requirements of Item 0107601.

CONSTRUCTION METHODS

Various types of portable sign supports may be used. These portable supports shall be fabricated in such a manner as to minimize the possibility of the signs being blown over or displaced by the wind from passing vehicles and are to be of a yielding type to withstand impact with minimal damage to signs, supports, and vehicles. Portable sign supports shall be approved by the City Traffic Engineer before they are utilized on the project site.

Suitable attachments shall be provided so that the signs can be firmly attached to the portable sign supports or metal posts without causing damage to the sign.

METHOD OF MEASUREMENT

Signs will be measured for payment by the number of square feet of construction signs delivered and used on the project.

BASIS OF PAYMENT

This item will be paid for by the number of square feet for "CONSTRUCTION SIGNS", used on the project, which price shall include the sign, portable sign support, metal sign posts and all hardware required to attach the sign to the support or posts. Said price shall also include all costs to maintain, move, adjust, relocate and store the signs. Each sign and support will be paid for only once. Any signs that become damaged, defaced, or illegible so they are no longer effective in the opinion of the Engineer shall be replaced at no cost to the City.

The Contractor shall promptly remove any signs and their portable sign supports or metal posts are no longer required on the project. Payment will not be made for any signs not approved by the Engineer.

<u>PAY ITEM</u>	<u>DESCRIPTION</u>	<u>PAY UNIT</u>
0107201	Construction Signs	SF